HouseWorkbench RESOURCE

Plan storage projects from an opening and a product label

https://houseworkbench.com/resources/plan-storage-projects/ · Published September 18, 2026

What this resource helps decide

Storage projects on this site span several distinct jobs: continuous shelving built to fit an opening, individually mounted floating shelves, sheet-material shelves cut to a cabinet's dimensions, and modular wall systems sold in fixed-size units. This resource explains what distinguishes these jobs and which measurement and calculation approach applies to each.

Facts to measure or read from the product label

Opening-based shelving, closet, pantry, needs a verified opening width and height, since shelf count and length both derive from those dimensions rather than being entered directly. Individually mounted shelving, floating shelves, bookcases, needs each shelf's own span and depth, since these are not built to fill a single opening the way closet shelving is. Sheet-material shelving, a cabinet shelf replacement, needs the exact cabinet opening dimensions the new shelf must fit, plus the sheet stock's own coverage rating. Modular wall systems, like garage wall storage, need a verified usable wall area and each module option's own coverage area and price from the manufacturer.

How the applicable calculation or comparison works

Continuous shelving divides an opening's width by a shelf count, or derives shelf count from height and a target vertical spacing, then converts the resulting total shelf length into stock pieces using the site's standard linear-stock method, with support or bracket count scaled to shelf count and depth. Individually mounted shelving sums each shelf's own span into a total linear stock requirement, with brackets counted per shelf rather than by spacing along a continuous run. Sheet-material shelving converts a shelf's area into a waste-adjusted sheet count using the site's package-plan method, since a cabinet shelf is a cut piece from a larger sheet rather than a length of linear stock. Modular wall systems divide a usable area by each module option's coverage to reach a module count, often compared across two module sizes to see which produces a lower total cost.

Common interpretation mistakes

The most common mistake is treating every storage job as the same continuous-shelving calculation, when a floating shelf, a cabinet shelf, and a closet shelf are three different jobs with three different inputs. A second mistake is using a wall's total dimension instead of its usable area for a modular system, without subtracting space taken by outlets, windows, or other fixtures that reduce what is actually available for storage modules. A third mistake, specific to deeper shelves, is using the same support count regardless of shelf depth, when a deeper shelf under real load benefits from additional center support that a shallower shelf does not need.

What the model cannot decide

No engine on this site can confirm that your wall framing can actually anchor a planned support or bracket at your chosen spacing, or that a modular system's specific weight rating covers what you intend to store. These depend on your wall's actual stud location and construction, and on the product's own published load rating checked against your real intended use, neither of which a quantity calculation evaluates on its own.

A practical handoff checklist

Before purchasing based on a storage plan from this site: confirm which job type your project actually is, opening-based, individually mounted, sheet-cut, or modular, and that you used the matching engine. Confirm wall framing or backing exists at every planned anchor point. For deeper or heavier-load shelving, confirm support count is adequate for the actual weight you plan to store, not just the site default. Confirm any modular system's stated weight rating against your heaviest planned item before finalizing a purchase.

Environment affects material choice as much as job type

A shed or garage storage project faces humidity and temperature swings an interior closet never does, which affects both hardware corrosion resistance and how forgiving standard lumber is over time. Favor galvanized or otherwise exterior-rated hardware for any storage project outside a climate-controlled space, even when the shelving itself is built from ordinary lumber, since standard interior hardware can corrode noticeably faster in an unheated, humid environment.

Multiple storage jobs in one project should be planned as separate line items

A single project, outfitting a garage or finishing a closet system, often combines more than one of these job types: continuous shelving along one wall, a modular system on another, and floating shelves for a display area. Run each portion through its matching engine separately rather than trying to force one calculation to cover a mixed layout, then sum the resulting costs into your overall project budget.

Linked engines

This resource explains the planning method behind Closet shelving plan, Closet rod plan, Kitchen cabinet hardware plan, Cabinet shelf replacement plan, Pantry shelving plan, Garage wall storage plan, Floating shelf plan, and Bookcase material plan.